

ELECTRIMOTION INC
1484 DALE FORD RD
DELAWARE OH 43015

CAM SYNC / 8771 ICT



CAM SYNC SET UP:

The magnet should be just entering the pickup at approximately 90 degrees before #1 TDC.